

<b>Wyoming Water Quality Application Form</b> <b>Permit to Construct Small Wastewater System</b> <b>Conventional Septic System with Leachfield less than 2,000 gallons per day only.</b> Not to be used for mound, evaporation ponds, or other non-conventional systems. For non-conventional system, contact district engineer. For systems exceeding 2,000 gallons per day, contact the Underground Injection Control Program at 307-777-7781 or refer to: <a href="http://deg.state.wy.us/wqd/groundwater/uicprogram/index.asp">http://deg.state.wy.us/wqd/groundwater/uicprogram/index.asp</a>		<b>WQD USE ONLY</b>	
		<b>App. No</b>	
		<b>Date</b>	
<b>Complete attached package and submit to appropriate office:</b>			
DEQ/ Water Quality Division 122 West 25 <sup>th</sup> Street Cheyenne, WY 82002 (307) 777-7781	DEQ/Water Quality Division 510 Meadowview Drive Lander, WY (307) 332-3144	DEQ/Water Quality Division 152 North Durbin Street, Suite 100 Casper, WY 82601 (307) 473-3465	
Please see: <a href="http://deg.state.wy.us/wqd/www/districts.pdf">http://deg.state.wy.us/wqd/www/districts.pdf</a> to locate nearest office.			
<b>Name of Project:</b>			
<b>Description of Project:</b>			
<b>Location:</b>	County:		
	¼ ¼ Section		Section
	Township		Range
	Subdivision Name		
	Lot and Block		
<b>Signatures: All undersigned agree to comply with the applicable Wyoming Statues and Regulations and to allow the activities described in this application.</b>			
<b>Real Estate Owner</b>	<b>Engineer/Geologist (required for all commercial systems)</b>		
<b>Sign Above</b>	<b>Sign Above</b>		
<b>Printed Name:</b>	<b>Printed Name:</b>		
<b>Title:</b>	<b>Title:</b>		
Mailing Address	Mailing Address		
City, State	City, State		
Zip	Zip		
Phone Number	Phone Number		
Email	Email		
	WY P.E.#	WY P.G.#	

# PROPERTY INFORMATION AND INSTALLER

<b>PROPERTY</b>	<b>County</b>	
	<b>Physical Address</b>	
	<b>Size</b>	feet by      feet <b>OR</b> acres
	<b>Type of Building</b>	
		(single family dwelling, mobile home, commercial, etc.)
<b>Water Source</b> Check one	<input type="checkbox"/> Private well                  SEO Well Number _____ <input type="checkbox"/> Cistern <input type="checkbox"/> Community Well _____ (name) <input type="checkbox"/> Municipal _____ (name)	
<b>Is the septic system in compliance with a county approved plat?    _____ Yes    _____ No</b>		
Attach the legal description of property (from Sales Contract or Deed)		
<b>Is this a replacement septic tank and/or leachfield?                                  _____ Yes    _____ No</b>		
<b>INSTALLER</b>	<b>Name</b>	
	<b>Mailing Address</b>	
	<b>City, State</b>	
	<b>Phone</b>	
	<b>Email</b>	
Additional comments:		

**Attach copy of legal description**

# SYSTEM DESIGN AND CONFIGURATION

<b>PLEASE CHECK ONE</b>	<input type="checkbox"/> <b>Permanent Structure (single family residence)</b>	_____ number of bedrooms x 150 gallons per day per bedroom = _____ gallons per day				
	<input type="checkbox"/> <b>Mobile Home (check one)</b>	<input type="checkbox"/> 1 or 2 bedrooms = 350 gallons per day <input type="checkbox"/> 3 bedrooms = 500 gallons per day <input type="checkbox"/> 4 bedrooms = 650 gallons per day				
	<input type="checkbox"/> <b>Non-residential</b>	Refer to Chapter 11, Part D, Table 1 (show calculations – use another sheet if needed)				
<b>DESIGN FLOW</b> gpd		Box 1  (from above)				
<b>PERCOLATION RATE</b> mpi		(from percolation test results – Page 8)				
<b>PLEASE CHECK ONE</b>	Perc. Rate	Loading Rate	Perc. Rate	Loading Rate	Perc. Rate	Loading Rate
	<input type="checkbox"/> 1 - 5	0.80	<input type="checkbox"/> 16	0.50	<input type="checkbox"/> 30-31	0.39
	<input type="checkbox"/> 6	0.75	<input type="checkbox"/> 17	0.49	<input type="checkbox"/> 32-33	0.38
	<input type="checkbox"/> 7	0.71	<input type="checkbox"/> 18	0.48	<input type="checkbox"/> 34- 35	0.37
	<input type="checkbox"/> 8	0.68	<input type="checkbox"/> 19	0.47	<input type="checkbox"/> 36- 38	0.36
	<input type="checkbox"/> 9	0.65	<input type="checkbox"/> 20	0.46	<input type="checkbox"/> 39 - 41	0.35
	<input type="checkbox"/> 10	0.63	<input type="checkbox"/> 21	0.45	<input type="checkbox"/> 42- 44	0.34
	<input type="checkbox"/> 11	0.60	<input type="checkbox"/> 22 - 23	0.44	<input type="checkbox"/> 45 - 47	0.33
	<input type="checkbox"/> 12	0.57	<input type="checkbox"/> 24	0.43	<input type="checkbox"/> 48 - 52	0.32
	<input type="checkbox"/> 13	0.55	<input type="checkbox"/> 25	0.42	<input type="checkbox"/> 53 - 56	0.31
	<input type="checkbox"/> 14	0.54	<input type="checkbox"/> 26 - 27	0.41	<input type="checkbox"/> 57 - 60	0.30
	<input type="checkbox"/> 15	0.52	<input type="checkbox"/> 28 - 29	0.40		
<b>LOADING RATE</b> gpd/ft <sup>2</sup>		Box 2  (from above chart)				
<b>LEACHFIELD SIZING</b> sq. ft.		Design flow (green box 1) / Loading rate (red box 2)  _____ / _____ =				
		Box 3  (from above)				

# Percolation Tests

In order for a septic system to perform properly, the wastewater needs to be effectively treated by the soil and percolate or travel through the soil in a reasonable amount of time to be appropriately treated.

## PERCOLATION TEST PROCEDURE INSTRUCTIONS

1. Location of Percolation Test Holes - The percolation (perc) test holes shall be spaced uniformly over the proposed soil absorption (leachfield) site. A **minimum of three (3) test holes** are required. More than 3 can be used if desired.

2. Test Hole Preparation - Test holes that are **4 to 12 inches** in diameter shall be dug or bored to the proposed depth of the leach field (typical depths are **30 to 40 inches**). The side walls shall be vertical and a natural soil surface (one which is not smeared from digging) shall be exposed by scraping the sides and bottom of the test hole with a sharp pointed instrument. Any loose material shall be removed from the test hole and several inches of course sand or gravel placed in the bottom of the test hole in order to prevent scouring and sealing before the water is poured in.


3. Presoaking - **PRESOAKING IS ABSOLUTELY REQUIRED** in order to get valid percolation test results. The purpose of presoaking is to have the water conditions in the soil reach a stable condition similar to that which exists during continual wastewater application in a leachfield. The minimum time of presoaking varies with soil type and presoaking instructions are usually sufficient to establish the proper soil moisture conditions.

a. *Sandy or loose soils* - Fill the test hole to within several inches of the top and allow it to seep away. Fill the hole a 2<sup>nd</sup> and 3<sup>rd</sup> time and let the water seep away. If the water continues to all seep away in ten (10) minutes or less, this indicates that the soil is excessively permeable and the site is unsuitable for a standard subsurface disposal system. In this case, special requirements are needed and you'll need to contact your County Official.

b. *Other suitable soils* - If the soil is suitable for a standard subsurface leachfield, then the test holes should be presoaked for at least 4 hours. Maintain at least 12 inches of water in the test holes for at least 4 hours, then allow the soil to swell for 12 hours (overnight is good) before starting the actual perc test measurements.

4. Percolation Rate Measurements - Start the test by filling each test hole with approximately **12 to 18 inches** of water. Let the soil re-hydrate for about 15 minutes and then refill to 12 to 18 inches deep. Next, decide on a time interval for your test. Time intervals of **10 or 15 minutes** are typical. Once decided, the time interval must remain constant throughout the test so that it can be determined when the water level drop rate has stabilized. Measure the initial water level (from a fixed reference point such as a flat board across the top of the hole) in each hole and record on the first line for each hole in the test data table. After each water level measurement, calculate the water level drop from the previous measurement and record in the test data table. Continue the test until the water

level drop rate has stabilized; i.e. - **3 consecutive equal drop rates** within 1/8 inch of each other. Please note that some test holes may take longer than others to stabilize. The test should be continued at each test hole until each drop rate stabilizes. Also please note, a minimum of **6 inches** of water should be maintained in the test hole. If the level drops below 6 inches, some additional water should be added between time intervals. If water level drops fluctuate, use the final of 6 intervals for calculations.



Side view of a typical percolation test. Yardstick is lowered to the surface of the water after each time interval. Time interval and measurement are noted and recorded. When measuring use the reference point as a guide.



# SITE SUITABILITY

The owner must be aware of the depth of the impermeable soil layer, the seasonally high groundwater level, and slope when considering the septic system location.

**Please check off the following and complete as indicated:**

<b>Excavation</b>	Was an excavation conducted within the proposed location of the leachfield?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	Was bottom of the excavation at least <b>4 feet below</b> the bottom of the proposed leachfield?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	Was a color photograph taken of the excavation, showing a tape measure? If so, please submit photograph with application.	<input type="checkbox"/> Yes <input type="checkbox"/> No
	Depth of Excavation?	
	Who conducted the excavation?	
	Date excavation was conducted?	
<b>Impermeable Layer</b>	Was a rock layer observed?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	If yes, at what depth below ground surface?	
	Was a clay layer observed?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	If yes, at what depth below ground surface?	
<b>Seasonal High Groundwater</b>	Was groundwater present in the excavation?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	If so, at what depth below ground surface?	
	Did the soil have a mottled color (which can be indicative of groundwater)?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	If so, at what depth below ground surface?	
	Was the soil stained a dark color or was a salt/alkali layer encountered?	<input type="checkbox"/> Yes <input type="checkbox"/> No
	If so, at what depth below ground surface?	
<b>Slope</b>	What is the estimated slope of the proposed leachfield area?	
	How far away is the nearest break in slope (such as the side of a hill)?	
	How far away is the nearest drainage ditch or surface water body, such as a river, pond, creek, etc.?	
	Was a color photograph taken of the proposed leachfield area?	<input type="checkbox"/> Yes <input type="checkbox"/> No


**Attach a color photograph of the excavation and proposed location of the leachfield.**

## SITE PLAN DRAWING

Provide a sketch of your site, showing the following (check off those items included on your site plan):

<input type="checkbox"/>	Property lines	<input type="checkbox"/>	Leachfield
<input type="checkbox"/>	All buildings	<input type="checkbox"/>	Replacement leachfield
<input type="checkbox"/>	Surface water (ditch, creek, pond, etc.)	<input type="checkbox"/>	Slope of land (drawn as an arrow indicating general slope direction)
<input type="checkbox"/>	Water lines	<input type="checkbox"/>	North arrow
<input type="checkbox"/>	All wells within 200 feet	<input type="checkbox"/>	Access road to house or driveway
<input type="checkbox"/>	Septic tank		

**Example site plan:**



**Your septic system MUST have the following minimum separation distances:**

From	To Septic Tank	To Leachfield
<input type="checkbox"/> Wells	50 feet	100 feet
<input type="checkbox"/> Open waterways	50 feet	50 feet
<input type="checkbox"/> Potable water lines	25 feet	25 feet
<input type="checkbox"/> Building foundation without foundation drain	5 feet	10 feet
<input type="checkbox"/> Building foundation with a foundation drain	5 feet	25 feet
<input type="checkbox"/> Break in slope	15 feet	15 feet
<input type="checkbox"/> Property line	10 feet	10 feet
<input type="checkbox"/> Septic tank	Not applicable	10 feet

**Attach a site plan.**

## COMPONENTS

<b>SEPTIC TANK</b>	Is the septic tank on the approved list?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	If yes, provide the following:	Manufacturer:		
		Model:		
		Size:		
	If no, provide the following <b>AND Complete septic tank design worksheet:</b>	Size of tank		
		Number of compartments		
		Tank material		
	For a 4-bedroom (or smaller) house, is the tank size 1,000 gallons or more?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	For homes greater than 4 bedrooms, does the tank have additional capacity of 250 gallons per additional bedroom?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
Estimated depth of backfill over tank?				
Is the tank equipped with a 6-inch cleanout that extends to the ground surface from each compartment of the tank?		<input type="checkbox"/> Yes	<input type="checkbox"/> No	
<b>PIPING</b>	What is the piping material from the house to the septic tank?			
	What is the pipe size?			
	Is the pipe from the house to the septic tank in a straight line?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	If no, will cleanout ports be installed at any alignment change greater than 22.5 degrees? <b>This is required.</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Is the pipe from the house to the septic tank greater than 100 feet?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	If yes, will cleanout ports be installed? <b>This is required.</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Is there a cleanout port just outside of the building? (encouraged, not required)		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Does the piping have a minimum slope of ¼ inch per foot (2%) for a 4-inch pipe?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Is there a distribution box on the effluent piping?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Are flow dividers installed on the effluent piping?		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Are all leachfield trenches less than 100 feet? <b>This is required.</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No
<b>LEACHFIELD DESIGN</b>	Are you using a pipe trench system? <b>IMPORTANT: Complete Part A</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Are you using a pipe bed system? <b>IMPORTANT: Complete Part B</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Are you using a chamber trench system? <b>IMPORTANT: Complete Part C</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No
	Are you using a chamber bed system? <b>IMPORTANT: Complete Part D</b>		<input type="checkbox"/> Yes	<input type="checkbox"/> No

# SEPTIC TANK DESIGN WORKSHEET

**(To be completed ONLY if tank is not on approved list)**

Material: \_\_\_\_\_


Inside Dimensions (in inches) \_\_\_\_\_

Length \_\_\_\_\_ Width \_\_\_\_\_ Height \_\_\_\_\_

Liquid Depth \_\_\_\_\_ Air Space \_\_\_\_\_

Operating Capacity = (Length \* Width \* Liquid Depth) / 231 = \_\_\_\_\_ Gallons

Fill in all blue boxes below.



All requirements listed below and shown on the illustration apply to any tank used or site-built:

1. All small wastewater systems using a septic tank must have a minimum operating capacity of 1,000 gallons. Additional capacity of 250 gallons per bedroom is required for each bedroom past four. Either one or two tanks may be used to meet this requirement.
2. The septic tank must be constructed of durable material not subject to rapid corrosion or decay and must be structurally sound and watertight. Steel tanks are not allowed.
3. Single compartment tanks shall have a minimum length to width ratio of 2:1.
4. Two compartment tanks shall have at least 50% of the volume in the first compartment.
5. Each compartment of the tank shall have an access opening with a minimum dimension of 20 inches in the least direction. Both inlet and outlet devices shall be accessible.
6. Clean-outs extending from each compartment to the surface with a minimum diameter of 6 inches must be provided. The access openings may be extended to the ground surface by use of a manway in lieu of a clean-out riser. All openings must be capped.